

15-015-30225-00-00 69

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Butler County, Sec. 22 Twp. 28 Rge. 3 (E) E(W)

Location as "NE/CNWKSX" or footage from lines. C W/2 SE NE

Lease Owner Tom-Kat, Inc.

Lease Name Swindell Well No. 3

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 8-30-66 19

Plugging completed 9-2-66 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Paul Turpin 3014

Producing formation Depth to top Bottom Total Depth of Well 3020 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	166'	None
				5-1/2"	3012'	2100'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3020', sanded hole to 3000' and dumped 5 sacks of cement @ 3000' with dump bailer. Pulled 5 1/2" casing, set rock bridge from 200' to 180' and dumped 20 sacks of cement @ 180'. Mudded hole to 35', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
9/14/66  
SEP 14 1966

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of September, 1966

Milton J. Volin Notary Public.

My commission expires May 20, 1968

DRILLER'S LOG

FARM NAME: SWINDELL #3 LOCATION: E/2 NE/4 Sec. 22-28S-3E  
 CONTRACTOR: Shawver Armour, Inc. Butler County, Kansas  
 OWNER: Tomlinson & Kathol ELEVATION: 1337 R. B.  
 COMMENCED: March 7, 1965 COMPLETED: March 13, 1965  
 CASING RECORD: 166' 8 5/8" w/125 sacks cement, 3 sacks cc

FORMATION:

TOPS

Top soil & clay 0-10  
 Lime 55  
 Shale 145  
 Lime & Shale 705  
 Shale 1285  
 Shale & Lime 1950  
 Lime 1990  
 Lime & Shale 2405  
 Lime 2490  
 Lime & Shale 2657  
 Lime 2760  
 Lime & Shale 2790  
 Lime 2956  
 Lime & Shale 3001  
 Shale 3011  
 Simpson Sand 3014  
 ROTARY TOTAL DEPTH 3014

Simpson Sand 3011  
 Mississippi Lime 2790

**RECEIVED**  
 STATE CORPORATION COMMISSION

AUG 4 1966

CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 SEDGWICK COUNTY ) ss

I, James M. Armour, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER ARMOUR, INC.

BY James M. Armour  
 James M. Armour

Subscribed and sworn to before me this 23rd day of March 1965.

My commission expires Dec. 10th, 1967

Claire Jones  
 Claire Jones, Notary Public