

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-101-22050-00-00 ⁰⁸⁵⁻²²⁰⁵⁰⁻⁰⁰⁻⁰⁰ *Op KCC* (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____

Well Operator: CORAL PRODUCTION CORP. KCC License #: 32639

Address: 1600 STOUT ST.; SUITE 1500 City: DENVER

State: COLORADO Zip Code: 80202 Contact Phone: (303) 623-3573

Lease: JOE BOB JAMES TRUST Well #: 8-1 Sec. 8 Twp. 16 S. R. 28 East West

NE SE SE Spot Location / QQQQ County: LANE

900 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 255.24' Cemented with: 170 Sacks

Production Casing Size: 5 1/2" Set at: 4313' Cemented with: 125 Sacks

List (ALL) Perforations and Bridgeplug Sets: PERFS: 4086'-4092', OPEN; 4262'-4266' OPEN;

Elevation: 2637' (G.L. / K.B.) T.D.: 4560' PBDT: 4295' Anhydrite Depth: 2036'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): SAND PLUG OVER PERFS; 10 SKS CEMENT ON TOP OF SAND; STRETCH CSG & SHOOT OFF; 30 SKS AT BASE OF SURFACE CSG, 1/2 IN, 1/2 OUT; 10 SKS @ SURFACE; CUT CSG 4' BELOW GRADE & WELD CAP

RECEIVED
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

JAN 16 2008

If not explain why? _____ CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: JOE BORLA

FIELD ENGINEER Phone: (303) 601-5823

Address: P.O. BOX 188 City / State: POTTER, NE

Plugging Contractor: Randall Quality Well Service KCC License #: 31925
(Company Name) (Contractor's)

Address: _____ Phone: ()

Proposed Date and Hour of Plugging (if known?): 1-21-08

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 1/10/08 Authorized Operator / Agent: J.R. Webb (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

* well plugged - kcc-dlg

Dist
01