

FEB 19 2008

Form CP-4

December 2003

CONSERVATION DIVISION  
WICHITA, KS  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Lease Operator: Baird Oil Company, LLC

Address: P.O. Box 428 Logan, KS 67646

Phone: ( 785 ) 689 - 7456 Operator License #: 32819

Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: January 11, 2008 (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Arbuckle Depth to Top: 3417 Bottom: 3440 T.D. 3440

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 163-23175 - 00 - 00

Lease Name: Griebel

Well Number: 5 *KCC Pkt Per CP 3*

Spot Location (QQQQ): 115'S of App - NW - SE - NE

3630 Feet from  North /  South Section Line

990 Feet from  East /  West Section Line

Sec. 20 Twp. 7 S. R. 19  East  West

County: Rooks

Date Well Completed: 8-2-1991

Plugging Commenced: 1-28-2008

Plugging Completed: 1-28-2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle		Surface	3417'	4 1/2"	3417'	None
	<i>OIL &amp; WATER</i>	Surface	209'	8 5/8"	209'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Well was plugged down casing from surface. Pumped 40 sks cement 60/40 poz 4% gel with 300# hulls, pumped 12 sks gel spacer with 400# hulls, pumped 95 sks cement to fill casing to surface. Pressured to 500psi. Pumped 15 sks cement down annulus at 300psi

Name of Plugging Contractor: Swift Services, Inc License #: 32382

Address: P.O. Box 466 Ness City, KS 67560


Name of Party Responsible for Plugging Fees: Baird Oil Company, LLC

State of Kansas County, Phillips, ss.

Andrew C. Noone (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *Andrew C. Noone*

(Address) P.O. Box 428 Logan, KS 67646



SUBSCRIBED and SWORN TO before me this 15<sup>th</sup> day of FEBRUARY, 20 08

*Robert B. Hartman* My Commission Expires: 3/29/2011  
Notary Public

*98*



P. O. Box 466  
 Ness City, KS 67560  
 Off: 785-798-2300



# Invoice

DATE	INVOICE #
1/28/2008	13159

BILL TO
Baird Oil Company LLC PO Box 428 Logan, KS 67646

- Acidizing
- Cement
- Tool Rental

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Job Purpose	Operator
Net 30	#5	Griebel	Rooks		Oil	Workover	PTA	Roger
PRICE REF.	DESCRIPTION				QTY	UM	UNIT PRICE	AMOUNT
575W	Mileage - 1 Way				50	Miles	4.00	200.00
576W-P	Pump Charge - PTA				1	Job	800.00	800.00
275	Cotton Seed Hulls				7	Sack(s)	28.00	196.00
581W	Service Charge Cement				190	Sacks	1.25	237.50
583W	Drayage				398.65	Ton Miles	1.00	398.65
326	60/40 Pozmix (2% Gel)				190	Sacks	9.50	1,805.00
279	Bentonite Gel				15	Sack(s)	24.00	360.00
	Subtotal							3,997.15

*2/16/2008*  
*2/17/2008*

*GRIEBEL*

*191020*

*3,997.15*

*GRIEBEL #5 - pump charge, cement and other misc. used to plug well*

RECEIVED  
 KANSAS CORPORATION COMMISSION  
**FEB 19 2008**  
 CONSERVATION DIVISION  
 WICHITA, KS

**Thank You For Your Business In 2007!**  
**We Look Forward To Serving You In 2008!**

**Total** \$3,997.15

*2/17/2008*  
*CK#7117*