

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: MIDCO Exploration, Inc.
Address: 414 Plaza Drive, Suite 204 Westmont, IL 60559
Phone: (630) 655 - 2198 Operator License #: 5254
Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 1/18/08 (Date)
by: Steve Durant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 025-21438-0000
Lease Name: Knight
Well Number: 1-19
Spot Location (QQQQ): NW - SE - SE -
990 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 19 Twp. 33 S. R. 23 East West
County: Clark
Date Well Completed: 1/18/08
Plugging Commenced: 1/20/08
Plugging Completed: 1/20/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Sand - clay		0	70	20"	70'	0
Shales		0	810	8 5/8"	810	0
Lime & shale		810	5750			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Heavy mud 5750-840' ; 50 sx @ 840' ; heavy mud 840-300' ; 40 sx at 300' ; heavy mud 300-60' ; 20 sx @ 60' ;
15 sx in rat hole; 10 sx in mouse hole; 60/40 poz 4% gel

Name of Plugging Contractor: VAL Energy License #: 5822

Address: 200 W Douglas, Suite 520 Wichita, KS 67202

Name of Party Responsible for Plugging Fees: MIDCO Exploration, Inc.

State of DuPage County, Illinois, ss.

Earl J. Joyce, Jr. (Employee of Operator), or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____


(Address) 414 Plaza Drive, Suite 204 Westmont, IL 60559

SUBSCRIBED and SWORN TO before me this 20th day of March, 2008

Nancy L. Macyunas
Notary Public

My Commission Expires: _____

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



RECEIVED
KANSAS CORPORATION COMMISSION
MAR 21 2008
CONSERVATION DIVISION
WICHITA, KS

PKJ