

API NUMBER 15-N/A

LEASE NAME Barry LKC Unit

WELL NUMBER 6W03

15-163-01623-00-01

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div. 42803650 Ft. from S Section Line
2310 4950 Ft. from E Section Line

LEASE OPERATOR Phillips Petroleum Company

SEC. 11 TWP. 9 RGE. 19 (E) or (W)

ADDRESS Route 3, Box 20A, Great Bend, Kansas 67530

COUNTY Rooks

PHONE# (316) 793-8421 OPERATORS LICENSE NO. 5229

Date Well Completed 10/19/48

Character of Well Injection

Plugging Commenced 09/26/94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 09/26/94

The plugging proposal was approved on 08/12/94 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation LKC 3187-3272 Depth to Top _____ Bottom _____ T.D. 3441

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4"	212	0
				6"	3431'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Pumped 15 bbl. wtr to clear tbq. Mixed & pmpd 100 sx 40/60 pozmix w/10% gel & 250# cotton seed hulls; pull tbq up to 2500' mixed & pmpd 100 sx 40/60 pozmix w/10% gel w/100 # hulls; pulled tbq to 1500', mixed & pmpd 100 sx 40/60 pozmix w/10% gel w/200# hulls. Cmt circulate to surface. Pull tbq. out of hole. RU to 10 3/4 x 6" annulus. Mixed & pmpd 40 sx 40/60 pozmix & 50 # hulls. Cmt circulate to surface out 6" csg. S.I. annulus w/150# pressure.

Name of Plugging Contractor Phillips Petroleum Company License No. 5229

Address Route 3, Box 20A, Great Bend, Kansas 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Phillips Petroleum Company

STATE OF Kansas COUNTY OF Rooks, ss.

Len G. Janson, Jr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Route 3, Box 20A, Great Bend, Ks. 67530



SUBSCRIBED AND SWORN TO before me this 28th day of September, 1994

Mary Augustine
Notary Public

My Commission Expires: 6-7-98
USE ONLY ONE SIDE OF EACH FORM

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1994
Form CP-4
Revised 05-88
DIVISION
WICHITA, KANSAS

W E L L L O G

Continental Oil Company

Described as your ^{Dan} Barry #3 Well,
located in Rocks County, Kansas.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface Soil	00	226
Shale & Shells	226	432
Sand, Shale & Shells	432	1130
Shale & Shells	1130	1390
Anhydrite	1390	1427
Shale & Shells	1427	1527
Shale & Shells	1527	1676
Shale & Lime	1676	1817
Shale & Lime	1817	1931
Shale & Lime	1931	1991
Shale & Lime	1991	2234
Lime & Shale	2234	2302
Shale & Lime	2302	2454
Lime & Shale	2454	2652
Lime & Shale	2652	2938
Shale & Lime	2938	3107
Shale & Lime	3107	3222
Lime & Shale	3222	3346
Lime & Shale	3345	3434
Total Depth	3434.	

copy to Pub. Dept., Wichita, 12-9-48

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1994

WICHITA, KANSAS