

To: 2 100320
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-20-88
API NUMBER 15- 015-22,768 -00-00 394

SE SW NW, SEC. 31, T 27 S, R 3 W/E

2310 feet from N/S section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Carney Well # C-1

Operator: TXO

County Butler 67.50

Name:

Well Total Depth 2077 PBD 2056 feet

Address 155 N. Market

Conductor Pipe: Size 4 1/2" feet 2077

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clark Corporation License Number 5105

Address Medicine Lodge, KS

Company to plug at: Hour: _____ Day: 19 Month: 5 Year: 19 88

Plugging proposal received from Jerry Collins

(company name) TXO (phone) _____

were: Pump 35 sxs on bottom, shoot and pull casing, pump 3 hulls, 10 gel and 100 sxs cement.

Plugging Proposal Received by J. L. Sanders (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:00pm Day: 20 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT Used 750 bbls water to kill well then pumped 30 sxs Class A cement on bottom w/plug. Shot and pulled 1750' of 4 1/2". Pumped on top 3 sxs hulls, 10 sxs gel and 100 sxs 60/40 pozmix

RECEIVED
6/3/88
JUN 5 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: United #1454 100# SI 225# oper.
(If additional description is necessary, use BACK of this form.)

INVOICED (If did or did not) observe this plugging.

DATE 6-28-88

Signed J. L. Sanders pd (TECHNICIAN)

INV. NO. 21096 5-20 AUG 10 1988