

10-12

2-050293

RECEIVED
KANSAS CORPORATION COMMISSION

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

OCT 18 1994

10-18-94

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-173-20,497⁻⁰⁰⁻⁰⁰ D-22,187

NW SE SE, SECTION 9 TOWNSHIP 28 RANGE 2E

OPERATOR LICENSE # 3095

990 FEET FROM S SECTION LINE
990 FEET FROM E SECTION LINE

OPERATOR PRAIRIE STATE PETROLEUM
NAME & P O BOX 305
ADDRESS LEON KS 67074

LEASE NAME: MOLLETT #4
COUNTY: SEDGWICK
WELL TOTAL DEPTH: 3380' 109.85

PIPE: 4-1/2" @ 3380'

SURFACE CASING: 8-5/8" @ 220'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: CLARKE CORPORATION
ADDRESS: 107 W FOWLER MEDICINE LODGE KS 67104 LICENSE: 5705

COMPANY TO PLUG AT: HOUR: 11:00 DAY: 12 MONTH: 10 YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: DIST 2
COMPANY NAME: UNITED CEMENTING PHONE: 316-321-4680

WERE: SAND BACK & SPOT 4 SX CMT @ 3340' - SHOOT 4-1/2" CSG
@ 2100' - PULL CSG TO 276' & CIRC CMT TO SURF - PULL
CSG OUT OF HOLE & TOP OFF W/CMT

PLUGGING PROPOSAL RECEIVED BY: JEFF SLETTO

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 13:00 DAY: 12 MONTH: 10 YEAR: 1994

ACTUAL PLUGGING REPORT:
SANDED BACK & SPOTTED 4 SX CMT @ 3340' - SHOT 4-1/2"
CSG @ 2100' - PULLED CSG TO 270' & CIRC CMT TO SURF
- PULLED CSG OUT OF HOLE & TOPPED OFF W/CEMENT


REMARKS: UNITED #1873 120 SX CMT 60/40 POZ 4% GEL

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 10-28-94

INV. NO. 41537


Jerry Clark

(AGENT)