

RECEIVED
KANSAS CORPORATION COMMISSION

10-5

2-050286

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

OCT 18 1994
10-18-94
CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-173-20,519-00-00

SE SE SE, SECTION 9 TOWNSHIP 28 RANGE 2E

OPERATOR LICENSE # 3095

330 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE

OPERATOR PRAIRIE STATES PETROLEUM
NAME & P O BOX 305
ADDRESS LEON KS 67074

LEASE NAME: MOLLETT #6

COUNTY: SEDGWICK 107.64
WELL TOTAL DEPTH: 3312'

PIPE: 5-1/2" @ 3310'

SURFACE CASING: 8-5/8" @ 212'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: CLARKE CORPORATION
ADDRESS: 107 W FOWLER, MEDICINE LODGE KS 67104 LICENSE: 5105

COMPANY TO PLUG AT: HOUR: 9:30 DAY: 5 MONTH: 10 YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: DISTRICT 2
COMPANY NAME: UNITED CEMENTING PHONE: 316-321-4680

WERE: SAND BACK & SPOT 4 SX CMT @ 2520' - SHOOT CSG & PULL TO 262' & CIRC CMT TO SURF - PULL CSG OUT OF HOLE & TOP OFF WITH CEMENT

PLUGGING PROPOSAL RECEIVED BY: JEFF SLETTO

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 11:00 DAY: 5 MONTH: 10 YEAR: 1994

ACTUAL PLUGGING REPORT:
SANDED BACK & SPOTTED 4 SX CMT @ 2520' - SHOT 5-1/2" CSG @ 1600' - PULLED CSG TO 264' & CIRC CMT TO SURF - PULLED CSG OUT OF HOLE AND TOPPED OFF WITH CMT


REMARKS: UNITED #1882 84 SX CMT 60/40 POZ 4% GEL

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 10-28-94

INV. NO. 415-39



Jerry Clark (AGENT)