

10-10

RECEIVED
KANSAS CORPORATION COMMISSION

2-050292

OCT 18 1994

10-18-94
CONSERVATION DIVISION
WICHITA, KS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-173-20,492-60-00

NE SE SE, SECTION 9 TOWNSHIP 28 RANGE 2E

OPERATOR LICENSE # 3095

990 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE

OPERATOR PRAIRIE STATE PETROLEUM
NAME & P O BOX 305
ADDRESS LEON KS 67074

LEASE NAME: MOLLETT #3
COUNTY: SEDGWICK
WELL TOTAL DEPTH: 3350' 108.87

PIPE: 4-1/2" N/A

SURFACE CASING: 8-5/8" @ 220'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: CLARKE CORPORATION
ADDRESS: 107 W FOWLER MEDICINE LODGE KS 67104 LICENSE: 5705

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 10 MONTH: 10 YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: DIST 2
COMPANY NAME: UNITED CEMENTING PHONE: 316-321-4680

WERE: SAND BACK & SPOT 5 SX CMT @ 3200' - SHOOT 4-1/2" CSG
@ 1950' - PULL CSG TO 270' & CIRC CMT TO SURF - PULL
CSG OUT OF HOLE & TOP OFF W/CMT

PLUGGING PROPOSAL RECEIVED BY: JEFF SLETTTO

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()


COMPLETED: HOUR: 14:00 DAY: 10 MONTH: 10 YEAR: 1994

ACTUAL PLUGGING REPORT:
SANDED BACK & SPOTTED 5 SX CMT @ 3200' - SHOT 4-1/2"
CSG @ 1950' - PULLED CSG TO 270' & CIRC CMT TO SURF
- PULLED CSG OUT OF HOLE & TOPPED OFF W/CEMENT

REMARKS: UNITED #1871 114 SX CMT 60/40 POZ 4% GEL

INVOICED
I DID OBSERVE THIS PLUGGING.

DATE 10-28-94
INV. NO. 41538



Jerry Clark (AGENT)