

2 060197

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-015-22,645-~~1000~~
SWN WSW SEC. 6, T 28 S, R 3 WE

1650 feet from N/S section line

4950 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5587

Lease Name Pray's Well # 2

Operator: Walter P. D.

County Butler 102.70

Name & Address 403 N. Hillcrest

Well Total Depth 3160 Simpson feet

Wichita, KS 67208

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well - Gas Well - Input Well - SWD Well - D&A X

Other well as hereinafter indicated -

Plugging Contractor White & Ellis License Number 5420

Address El Dorado, Kansas 67012

Company to plug at: Hour: - Day: 9 Month: 12 Year: 1984

Plugging proposal received from Ken Lore

(company name) White & Ellis (phone) -

were: fill hole with mud.

35 SPS at 260

25 SPS at 60

10 SPS in P.H.

Plugging Proposal Received by B. Tomer Selva
(TECHNICIAN)

Plugging Operations attended by Agent?: All - Part - None X

Operations Completed: Hour: 4:30 Day: 9 Month: 12 Year: 1984

ACTUAL PLUGGING REPORT

Filled hole with mud. Ran drill pipe to
approx 260' & dumped cement spotted 35 SPS. Com. Cement
40% gel & 30% CC. Pulled drill pipe to 60' & circulated
25 SPS to surface. Ran 1 quart drill pipe in hole & circulated
10 SPS Com 30% CC 40% gel to surface

Remarks: Techn 6811
(If additional description necessary, use BACK of this form.)

INVOLVED
DATE 12-19-84
INV. NO. 6054

RECEIVED
STATE CORPORATION COMMISSION
12/12/84
DEC 12 1984
Signed B. Tomer Selva
(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas