

15-015-19815-00-00

744-8071

2-050433

KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2125
Wichita, KS 67202

9-21-95

API NUMBER: 2/23/1951

SW SW NE SEC 5, T 28 S, R 3E

OPERATOR LICENSE # _____

2970 FEET FROM S SECTION LINE

OPERATOR: John Stephens

2310 FEET FROM E SECTION LINE

NAME & 501 E. 63rd North

LEASE NAME: Dinkler WELL # 1

ADDRESS: Wichita, KS 67219

COUNTY: Butler

P.O. Box 782257
WICHITA, KS 67258

WELL TOTAL DEPTH: 3056' 99.32

CONDUCTOR PIPE: 5 1/2" @ 3044'

SURFACE CASING: 8 5/8" @ 60'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____
OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR Hogoboom Well Service
ADDRESS: 767 Oil Hill Road, El Dorado, KS 67042 LICENSE: 7971

COMPANY TO PLUG AT: HOUR: 16:00 DAY: 21 MONTH: Sept. YEAR: 1995

PLUGGING PROPOSAL RECEIVED FROM District II

COMPANY NAME: United Cementing PHONE: 316-321-4680

WERE: Run tubing to 2700' and spot 50 sacks cement. Pull tubing out of hole. Perforate 5 1/2" casing at 250' and circulate cement to surface.

PLUGGING PROPOSAL RECEIVED BY: Albert Hogoboom

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { }

COMPLETED: HOUR: 18:00 DAY: 21 MONTH: Sept YEAR: 1995

ACTUAL PLUGGING REPORT: Ran tubing to 2700' and spotted 50 sacks cement. Pulled tubing out of hole. Perforated 5 1/2" casing at 250' and circulated cement to surface.

REMARKS: United #2477. 164 Sacks Cement. 60/40 Poz 2% Gel

I DID OBSERVE THIS PLUGGING.

Jerry Clark RECEIVED
KANSAS CORPORATION COMMISSION AGENT

3/5/96
MAR 05 1996

FORM CP-2/3
REV. 3/90

INVOICED

DATE MAR 05 1996 - 4-19-96

INV. NO. 44926

CONSERVATION DIVISION
WICHITA, KS