

2-031034 284
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-015-22,671-00-00

NE, SECTION 9 TOWNSHIP 28 RANGE 3E

OPERATOR LICENSE # 9913 4510 FEET FROM S SECTION LINE
1860 FEET FROM E SECTION LINE

OPERATOR Bullseye Petroleum, Inc.
NAME & 15820 Plymouth, Box 781925
ADDRESS Wichita, KS 67278

LEASE NAME: Hooper #3
COUNTY: Butler 101.56
WELL TOTAL DEPTH: 3125' PB 3114'

PIPE: 4-1/2" @ 3120'/50 sx
SURFACE CASING: 8-5/8" @ 209' CTS

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: McPherson Drilling Company
ADDRESS: RR #2, Box 168D, Augusta, KS 67010 LICENSE: 5495

COMPANY TO PLUG AT: HOUR: _____ DAY: 10 MONTH: 7 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Bill McPherson
COMPANY NAME: McPherson Drilling Co. PHONE: 316-775-3078

WERE: Sand hole 50' above perfs - dump 5 sx cmt - shoot &
pull csg - set rock bridge 300' to 250' - cmt to surf.
Perfs 3081' to 3083'

PLUGGING PROPOSAL RECEIVED BY: District #2 office

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: _____ DAY: 19 MONTH: 7 YEAR: 1991

8/2/91
AUG 2 1991
CONSERVATION DIVISION
Wichita, Kansas

ACTUAL PLUGGING REPORT:

Graveled to 2995' - dumped 4 sx cmt/bailer - shot &
pulled 2375' of 4-1/2" csg - ran 2-3/8" tub to 270' -
Knebler Concrete #034401 dumped 6-1/2 yds slurry mix
to surface - pulled tub - filled hole.

REMARKS: _____

I DID OBSERVE THIS PLUGGING.

INVOICED

Don Thompson
Don Thompson (AGENT)

DATE 8-23-91

INV. NO. 32758

DW