

To: 2 100260
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 015-22,789 - 00-00
SW NW NE, SEC. 9, T 28 S, R 3 XW/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 9913
Operator: Bullseye Petroleum
Name &
Address 500 N. Sage Brush
Wichita, KS 67230
(316) 733-5280

4290 feet from S section line
2310 feet from E section line
Lease Name C-J Hooper Well # 5
County Butler 101.37
Well Total Depth 3119 feet
Conductor Pipe: Size 4 1/2" feet 3118 75 sxs
Surface Casing: Size 8 5/8 feet 212 85 sxs

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor B & S Well Service± License Number 6013
Address Box 837, Winfield, KS

Company to plug at: Hour: PM Day: 6 Month: 8 Year: 1987

Plugging proposal received from William Ash
(company name) B & S Well Service (phone) (316)221-2036

work: Fill with chat to 3030' and dump 4 sxs cement. Shoot and recover casing, set
bridge from 275 to 250. Dump 5 yards of redimix.

RECEIVED
STATE CORPORATION COMMISSION
9/15/87
SEP 15 1987

Plugging Proposal Received by J. L. Sanders
CONSERVATION DIVISION
Wichita, Kansas
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7:30pm Day: 6 Month: 8 Year: 1987

ACTUAL PLUGGING REPORT Filled with chat to 3030' and dumped 4 sxs cement. Shot and
pulled 2300' of 4 1/2" and pumped 115 sxs of cement with 1 sxs hulls

Remarks: United Cementing #3328 60/40 No poz mix
(If additional description is necessary, use BACK of this form.)

INVOICED
did/did not observe this plugging.

DATE 9-21-87

INV. NO. 18153

Signed J. L. Sanders
(TECHNICIAN)