

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23487-00-00  
Spot: NWSEWNWNE Sec/Twnshp/Rge: 27-13S-13W  
960 feet from N Section Line, 1660 feet from E Section Line  
Lease Name: REINHARDT D Well #: 1  
County: RUSSELL Total Vertical Depth: 3360 feet

Operator License No.: 5135  
Op Name: FARMER, JOHN O., INC.  
Address: 370 W WICHITA AVE PO BOX 352  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	436		

109.20

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/28/2008 9:15 PM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 165 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE WitnessType: NONE  
Date/Time Plugging Completed: 02/29/2008 1:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

1st. Plug at 3275' w/25 sxs.  
2nd. Plug at 810' w/25 sxs.  
3rd. Plug at 490' w/80 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Perfs:

RECEIVED  
KANSAS CORPORATION COMMISSION  
  
APR 10 2008  
  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
DATE 4-21-08  
INV. NO. 2008061549

Remarks: ALLIED CEMENTING COMPANY

Plugged through: DP

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

Form CP-2/3

MAR 31 2008

PJT