

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20692-00-00
Spot: E2NENE Sec/Twnshp/Rge: 14-1S-35W
4620 feet from S Section Line, 330 feet from E Section Line
Lease Name: BURCH-SAVAGE Well #: 1
County: RAWLINS Total Vertical Depth: 4350 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 4352 | 0 | 440 SX |
| SURF | 8.625 | 305 | 0 | 200 SX |

141.38

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/31/2008 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (316) 263-3535

Proposed Plugging Method: Ordered 175 sxs 60/40 pozmix - 4% gel - 300# hulls - 30 sxs gel.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/31/2008 2:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 305' w/200 sxs cement.
5 1/2" production casing set at 4352' w/440 sxs cement.
PBTD 4323'. TD 4350'.
Ran tubing to 3700' - pumped 50 sxs cement with 300# hulls.
Pulled tubing to 3040' - pumped 30 sxs gel - gel to surface.
Pulled tubing to 350' - pumped 80 sxs cement - cement to surface.
Pulled tubing to surface. Connected to 5 1/2" production casing - pumped 5 sxs cement.
Connected to 8 5/8" surface pipe - pumped 40 sxs cement.
Max. P.S.I. 375#. S.I.P. 0#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4270 | 4274 | | |
| 4179 | 4187 | | |
| 4132 | 4134 | | |
| 4078 | 4080 | | |
| 4026 | 4028 | | |

RECEIVED
KANSAS CORPORATION COMMISSION
APR 10 2008
CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 4-21-08
INV. NO. 2008061550

Remarks: SWIFT SERVICES, INC.-TICKET #14008.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

APR 01 2008

PJT