

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05290-00-00
Spot: SESENW Sec/Twnshp/Rge: 14-12S-18W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: JOY Well #: 1
County: ELLIS Total Vertical Depth: 3669 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3663	0	w/125 sxs cmt
SURF	8.625	1410	0	w/700 sxs cmt

119.24

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2008 11:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DAVE JENSON Company: LARIO OIL & GAS COMPANY. Phone: (316) 259-1778

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 12 sxs gel - 600# hulls.
Well was squeezed in 1982 at 120' w/250 sxs and 2596'-2970' w/350 sxs.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2008 4:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Ran in hole with tubing to 3401' - rigged to tubing - pumped 12 sxs gel followed with 60 sxs 60/40 pozmix - 4% gel with 150# hull mixed in.
Pulled tubing to 1850' - rigged to tubing - pumped 140sxs 60/40 pozmix - 4% gel with 450# hulls mixed in to circulate cement to surface.
Pulled tubing - rigged to 5 1/2" casing with a swedge - pumped 25 sxs cement.
Max. P.S.I. 600#. S.I.P. 450#.
Dug out 8 5/8" backside - pulled bull plug.
Backside full of cement - visual check.

Perfs:

Top	Bot	Thru	Comments
3664	3669	OH	

RECEIVED
KANSAS CORPORATION COMMISSION
APR 10 2008
CONSERVATION DIVISION
WICHITA, KS

INVOICED

Remarks: ALLIED CEMENTING COMPANY-TICKET #24843.

DATE 4/21/08
INV. NO. 2008061553

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN) cm

APR 08 2008

PKT

LARIO OIL & GAS CO.

#1

JOY

14-12-18W
SE SE NW

Contr.

ELLIS

County

E 2151RB

Comm.

Comp.


11-11-49

IP

25 BOPD & 71% WTR

Tops	Depth	Datum
TOP	3131	-980
LANS	3396	-1245
STMP	3647	-1496
ARB	3661	-1510
T.D.	3669	-1518

Casing
 8" 1410 6 BFPH
 5" 3663 RMP 25 BO & 70% WTR/
 24 HRS



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS