

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20269-00-00

Spot: NWSENE

Sec/Twnshp/Rge: 28-14S-14W

3630 feet from S Section Line,

990 feet from E Section Line

Lease Name: OLSON A J B

Well #: 7

County: RUSSELL

Total Vertical Depth: 3370 feet

Operator License No.: 33699

Op Name: T-N-T ENGINEERING, INC.

Address: 3711 MAPLEWOOD STE 201
WICHITA FALLS, TX 76308

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		2981		
PROD	5.5	3363	1670	350 SX <u>109.53</u>
SURF	8.625	835	0	450 SX

Well Type: EOR

UIC Docket No: E04587.14

Date/Time to Plug: 03/27/2008 2:00 PM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICKEY POPP

Company: T-N-T ENGINEERING, INC.

Phone: (620) 727-3410

Proposed
Plugging
Method:

Ordered 275 sxs 60/40 pozmix - 4% gel - 750# hulls.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/27/2008 6:00 PM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded in bottom to 2980' - dumped 5 sxs on top. Cut casing at 1670'.
Pulled to 1450' - tied onto casing - pumped 100 sxs cement with 300# hulls.
Pulled to 850' - pumped 35 sxs cement with 150# hulls.
Pulled to 550' - pumped 50 sxs cement with 200# hulls.
Pulled to 200' - pumped 90 sxs cement with 100 # hulls.
Cement circulated to top. Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3302	3308		
3273	3293		
3258	3266		
3193	3196		
3168	3174		
3090	3102		
3038	3042		

RECEIVED
KANSAS CORPORATION COMMISSION

APR 10 2008

CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 4-21-08
INV. NO 2008061562

Remarks: QUALITY CEMENTING COMPANY-TICKET #1797.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

cm

MAR 31 2008

PPT

PAN AMERICAN PETROLEUM CORP.
LIBERAL, KS.

#7 A.J. OLSON 'B'

28-14-14W

NW SE NE

Contr. MURFIN DRUG. CO.

Cty. RUSSELL

Geol.

Pool HALL-GURNEY

E. 1819 KB Cm. 12/22/68 Cp. 1/23/69 IP WTR INJECT-RATE

OK/LANS 3038-3308

API 15-167-20,269

SMP Tops

Depth

Datum

Csg. 8" 835

5 1/2" 3363

ANH 824

+ 995

TARK 2382

- 563

TOP 2702

- 883

LANS 2998

- 1179

TD 3370

- 1551

CO PF LANS 'M', 3302-08, A 1000,
SWB 85 BLW; PF 3273-79/ A 2000,
PF 3258-66, A 3000, SWB 88 BLW,
SWB 8.35 BFPH, 5% OIL, PF 3193-96,
A 1000, SWB 1.26 BLWPH/3 HRS, RE-
A (3193-96) 2000, SWB 1.26 BFPH,
TR/OIL/6 HRS, PF 3168-74, A 1250,
SWB 25 BLW, SWB 6.68 BFPH, 1%
OIL; PF 3090-3102, FP 3038-42, A
1250, SWB 1 BWPH, 1% W, SET TBG
W/PKR 2981

NO LOG

NO DSTS

NO CORES

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS