

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-20338-00-00
Spot: SESWSWSE Sec/Twnshp/Rge: 9-26S-18E
300 feet from S Section Line, 2095 feet from E Section Line
Lease Name: MONARCH Well #: 3
County: ALLEN Total Vertical Depth: 775 feet

Operator License No.: 5488
Op Name: TWM PRODUCTION CO., A GENERAL P
Address: 1150 HWY 39
CHANUTE, KS 66720

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD | 2 | 775 | 0 | |
| SURF | 6 | 20 | 0 | |

35.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/18/2008 10:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE WIMSET Company: W & W PRODUCTION CO. Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO 775' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 02/18/2008 11:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 700PSI. 31 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs: **INVOICED**
DATE 4-21-08
INV. NO. 2008061563

RECEIVED
KCC DISTRICT #3

MAR 26 2008 CPT

CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION
APR 10 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: SPOT LOCATION FOR THIS WELL WAS ESTABLISHED FOR THIS WELL VIA GPS AS 300'NSL & 2095' WEL OF S.9.

Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

Handwritten initials