

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-21111-00-00
Spot: SWSNWSE Sec/Twnshp/Rge: 9-26S-18E
1378 feet from S Section Line, 1806 feet from E Section Line
Lease Name: MONARCH Well #: 14
County: ALLEN Total Vertical Depth: 775 feet

Operator License No.: 5488
Op Name: TWM PRODUCTION CO., A GENERAL P
Address: 1150 HWY 39
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2	775	0	
SURF	6	20	0	35.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/18/2008 11:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE WIMSET Company: W & W PRODUCTION CO. Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO 775" THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 02/18/2008 12:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 750 PSI. 33 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

RECEIVED
KCC DISTRICT #3

MAR 26 2008

CHANUTE, KS

CPT

RECEIVED
KANSAS CORPORATION COMMISSION

APR 10 2008

CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 4-21-08
INV. NO. 2008061563

Remarks: SPOT LOCATION FOR THIS WELL WAS ESTABLISHED VIA GPS AS 1378' NSL & 1806' WEL.

Plugged through: CSG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

CPT