

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-20563-00-01  
Spot: SWSW Sec/Twnshp/Rge: 12-26S-6W  
636 feet from S Section Line, 4756 feet from E Section Line  
Lease Name: FLICKNER Well #: 1  
County: RENO Total Vertical Depth: 4159 feet

Operator License No.: 33324  
Op Name: ALLAM PRODUCTION, INC.  
Address: PO BOX 2325  
HUTCHINSON, KS 67504

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4159	7		
SURF	264	10		

135.17

Well Type: SW UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/10/2008 8:00 AM  
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.  
Proposal Rcvd. from: DUB ALLAM Company: ALLAM PRODUCTION, INC. Phone: (620) 465-2337

Proposed Plugging Method: SET C.I.B.P. @ 31,185' & TOP WITH 7 SXS. CEMENT. PERFORATE 7" CASING @ 750' & 350'. RUN TUBING TO 750' & SPOT 50 SXS CEMENT. PULL TUBING TO 350' & CIRCULATE CEMENT TO THE SURFACE IN 7" & 9 7/8" ANNULUS.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/10/2008 1:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

SAT C.I.B.P. @ 3,185' & TOPPED WITH 7 SXS. CEMENT. PERFORATED 7" CASING @ 750' & 350'. RAN TUBING TO 748' & SPOTTED 50 SXS. CEMENT. PULLED TUBING TO 358' & CIRCUALTED 175 SXS. CEMENT TO THE SURFACE INSIDE 7" CASING & IN 9 7/8" X 7" ANNULUS.

Perfs:

**INVOICED**  
DATE 4-23-08  
INV. NO. 2008041574

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 17 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY CONSOLIDATED OILWELL SERVICES, LLC. INVOICE #13035.

Plugged through: TBG

District: 02

Signed Michael Wilson  
(TECHNICIAN)

*Handwritten initials*