

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-12246-00-00
Spot: SESWNE Sec/Twnshp/Rge: 29-20S-12W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MCCULLOUGH-BRYANT B Well #: 3
County: BARTON Total Vertical Depth: 3460 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N MARKET STE 1130
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3453	0	w/unknown sxs cmt
SURF	8.625	279	0	w/unknown sxs cmt

112.45

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2008 9:00 AM
Plug Co. License No.: 5042 Plug Co. Name: EDMISTON OIL COMPANY, INC.
Proposal Rcvd. from: DALE MAY Company: EDMISTON OIL COMPANY, INC. Phone: (620) 792-6924

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 700#hulls.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/04/2008 1:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:
Ran tubing to 3400' - pumped 15 sxs gel - 50 sxs cement with 200# hulls.
Pulled to 1500' - had color.
Pulled to 600' - pumped 100 sxs cement with 150# hulls - circulated to top.
Pulled tubing - topped off with 5 sxs. S.I.P. 200#.
Tied to backside - pressured up full.

Perfs:
INVOICED
DATE 4/23/08
INV. NO 2008061581

RECEIVED
KANSAS CORPORATION COMMISSION
APR 14 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #33212.
Plugged through: CSG

District: 04 Signed Bruce Rodie (TECHNICIAN) CM

Form CP-2/3
[Signature]

APR 09 2008

S3

29-20-12W

E K EDMISTON

#3 MCCULLOUGH-BRYANT 'B' SE SW NE

Contr. E K EDMISTON BARTON County

E 1854 RB Comm. Comp. 8-26-60 IP 90 BOPD

Tops	Depth	Datum	Casing
HEEB	3056	-1202	8" 279
			5" 3453
BR LM	3178	-1324	DST 3453-60/90", 85' MDY GSY O, BHP 1040-850#
LANS	3194	-1340	FU 200' O/12 HRS, NW: 10 GOPH, NATL: ACID 300: 200' OIH/12 HRS
B/KC	3421	-1567	25 GOPH: ACID 1000: 1/2 BOPH: DD
CONG	3431	-1577	3472: SWB 3 BOPH: FU 950' OIH/ 12 HRS: FU 1000' OIH/12 HRS
ARB	3451	-1597	
TD	3460	-1606	

WORKMAN WEST POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

[Handwritten notes]

[Handwritten notes]