

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-141-20364-00-00
Spot: E2NWNE Sec/Twnshp/Rge: 32-9S-12W
4620 feet from S Section Line, 1650 feet from E Section Line
Lease Name: KENDIG Well #: 1-32
County: OSBORNE Total Vertical Depth: 3400 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3400	1600	100 SX CMT.
SURF	8.625	240	0	160 SX CMT. 110.50

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2008 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: MR. ROB LONG Company: HOLL, F.G., COMPANY LLC Phone: (620) 793-0915

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls.
Remove 1600' casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2008 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Sanded off at 3175' with 4 sxs. Cut casing at 1600'.
Pulled 50' casing to 1550' - pumped 100 sxs cement with 300# hulls.
Pulled 1100' - pumped 35 sxs cement with 100# hulls.
Pulled 800' - pumped 35 sxs cement with 100# hulls.
Pulled to 200' - circulated cement with 65 sxs.
Pulled casing out - done.

Perfs:

Top	Bot	Thru	Comments
3261	3263		
3255	3258		LKC
3226	3233		LKC

INVOICED
DATE 4-23-08
INV. NO. 2008061590

RECEIVED
KANSAS CORPORATION COMMISSION
APR 14 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY CEMENTING COMPANY-TICKET #1850.

Plugged through: CSG

District: 04

Signed [Signature]
(TECHNICIAN)

WILDCAT

F G HOLL COMPANY LLC
WICHITA KS 67206

32-09S-12W
C E/2 NW NE

#1-32 KENDIG

site: 13-3/4 S & 1/2 E OF OSBORNE KS	co: OSBORNE	API 15-141-20364	<table border="1"> <tr><td></td><td></td><td>+</td><td></td></tr> <tr><td></td><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td><td></td></tr> </table>			+													
		+																	
contr: BERENTZ DRILLING #6	field: WC (1 W OF POTTERVILLE)																		
op: BILL G. REE																			
fr date: 09/25/2006	spd date: 09/28/2006	drig comp: 10/14/2006	card issued: 02/05/2007	last revised: 02/05/2007															

ELV: 1969 KB, 1964 GL SMP
 tops.....depth/datum
 SC.....1079 +890
 RTD.....4295 -2326
 NO OTHER TOPS RPTD
 LOGGED

IP status
 D&A, ARB, 01/10/2007
 CSG: 8-5/8" 240 / 160 SX (ALT 2), 4-1/2" 3400 / 100 SX
 COMMENT: MI & RURT 9/28/2006
 NO CORES
 DSTS TAKEN - DETAILS NA
 TRGT ZN: LKC (OIL/GAS), PTD 4300 (ARB), MICT (12/8/2006)
 - CO, PF (LKC) INTV NA, AC'D, SWB LD, NON-PROD, SI -
 EVAL, DECISION MADE TO P & A 1/10/2007 - TIGHT HOLE -
 NO OTHER INFO AVAILABLE - TEMP COMP 2/5/2007

COPYRIGHT 2008
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

117-20