

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19198-00-00
Spot: SWNENW Sec/Twnshp/Rge: 33-11S-19W
4290 feet from S Section Line, 1650 feet from W Section Line
Lease Name: SOLOMON Well #: 8
County: ELLIS Total Vertical Depth: 3642 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 1700 N WATERFRONT PKY BLDG 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3640	0	50 SX
SURF	8.625	108	0	125 SX

118.37

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2008 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEN WERNER Company: KNIGHTON OIL COMPANY, INC. Phone: (785) 623-4081

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 200# hulls.
Old squeeze: 739' to surface in 1955.
Tubing stuck- shot off at 1810'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2008 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes at 1450'.
Ran tubing to top of fish 1810'.
Allied pumped 100 sxs 60/40 pozmix - 4% gel neat - good circulation.
Pulled tubing to 900' - pumped 50 sxs cement - cwc.
PTOH. Squeezed 4 1/2" drill pipe with 160 sxs cement.
Max. P.S.I. 500#. S.I.P. 0#.
Backside pumped 40 sxs.
Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3640	3642	OH	

INVOICED
DATE 4-23-08
INV. NO 2008061591

RECEIVED
KANSAS CORPORATION COMMISSION

APR 14 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

APR 09 2008

PKT