

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-24346-00-00  
Spot: SWSENESE Sec/Twnshp/Rge: 28-11S-19W  
1410 feet from S Section Line, 450 feet from E Section Line  
Lease Name: BERLAND Well #: 10  
County: ELLIS Total Vertical Depth: 3700 feet

Operator License No.: 5010  
Op Name: KNIGHTON OIL COMPANY, INC.  
Address: 1700 N WATERFRONT PKY BLDG 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3694	0	400 SX CMT.
SURF	8.625	216	0	150 SX CMT.

| 20.25

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/07/2008 2:00 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: KEN WERNER Company: KNIGHTON OIL COMPANY, INC. Phone: (785) 623-8516

Proposed Plugging Method: 04/07/2008 - Ordered out 350 sxs 60/40 pozmix - 4% gel - 500# hulls.  
04/08/2008 - Ordered out 350 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Squeezed 1360'-1361' w/310 sxs.  
Tite spot at 1750'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/08/2008 10:30 AM KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

04/07/2008  
Perforated two holes at 1420'. Unable to get below 1758' casing.  
Ran tubing to 1850' - tite - unable to get tubing below. Pulled one joint at 1820'.  
Allied pumped 100 sxs neat - followed with 100 sxs cement with 250# hulls - no circulation.  
Pulled tubing to 1420'. Allied pumped 100 sxs cement with 250# hulls - no circulation. PTOH.  
04/08/2008  
Ran tubing in - tagged cement at 1302'. Pulled to 1290'.  
Allied pumped 65 sxs cement with 200# hulls - cwc.  
PTOH. Topped 5 1/2" casing with 10 sxs - casing full.  
Hooked up to backside - pumped 5 sxs.  
Max. P.S.I. 500#. S.I.P. 500#.

**Perfs:**

Top	Bot	Thru	Comments
3643	3647		
3631	3634		
3627	3629		
3506	3510		
3105	3110		

**INVOICED**  
DATE 4-23-08  
INV. NO 2008061591

RECEIVED  
KANSAS CORPORATION COMMISSION  
**APR 14 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.  
Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN) CM

APR 09 2008

KNIGHTON OIL COMPANY, INC.  
710 PETROLEUM BLDG.

#10 BERLAND


28-11-19W  
1410 FSL&

WICHITA, KS. 67202

450 FEL, SL 72

CONTR WESTERN KANSAS DRILLING CTY ELLIS

GEOLOGICAL FIELD SOLOMON



ELV 2120 KB SPD 10/30/85 CARD ISSUED 2/27/86 IP P 10 BO & 200 BWPD  
2115 GL DRLG COMP 11/9/85 ARB 3627-3634 OA

LOG	Tops	Depth/Datum
ANH	1409+	711
B/ANH	1449+	671
TOP	3075-	955
HEEB	3300-	1180
TOR	3318-	1198
LANS	3340-	1220
BKC	3567-	1447
CONG	3596-	1476
SIMP	3610-	1490
ARB	3631-	1511
PBTD	3661-	1541
RTD	3700-	1580

API 15-051-24,346

8 5/8 " 216 / 150SX, 5 1/2 " 3694 / 400SX  
NO CORES OR DST'S  
MCT - CO, PF (DAK) 1360-1361, W / 4 SPF, SWB DWN, SQZD  
PFS W / 310SX, CO CMT, PF (ARB) 3627-3629 & 3631-3634, W /  
4 SPF, SWB DWN, GSO, T&R, POP, P 10 BO & 200 BWP, 12/20/  
85

COPYRIGHT 1985  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

Handwritten notes: 28-11-19W, 1410 FSL&

Handwritten notes: 11, 12