

15-015-19758-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Butler County. Sec. 3 Twp. 27 Rge. 3 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SEC SW/4

Lease Owner Mr. J. P. Gaty

Lease Name Kiser Well No. 1

Office Address c/o Beech Aircraft Corp., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 30 19 53

Application for plugging filed Verbal April 30 19 53

Application for plugging approved Verbal April 30 19 53

Plugging commenced April 30 19 53

Plugging completed April 30 19 53

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lawrence Matthews, Jr., El Dorado, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3084 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy rotary mud to 90'. Set 10 sacks cement on wooden plug at 90'.
Filled with mud to surface and capped with 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morrison Drilling Company, Inc.

Address Drawer 712, El Dorado, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

John P. Gaty (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John P. Gaty

11 Cypress Dr. Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of May 1953

Eduard G. Hayes
Notary Public.



PLUGGING
FILE SEC 3 T 27 R 3E
BOOK PAGE 28 LINE 35

RECEIVED
STATE CORPORATION COMMISSION
5/7/53
MAY - 7 1953
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG - Kiser #1

OPERATOR: Mr. J. P. Gaty
c/o Beech Aircraft Corp.
Wichita, Kansas

LOCATION: SEc SW/4
Section 3-27-3E
Butler County, Kansas

CONTRACTOR: Morrison Drilling Company, Inc.
Drawr 712
El Dorado, Kansas

PRODUCTION: D & A

Farm: Kiser Well No. 1

Date Commenced: April 23, 1953
Date Completed: April 30, 1953

Total Depth: 3084 - Rotary

<u>From</u>	<u>To</u>	<u>Formation</u>
29	64	Cement
64	250	Shale and Lime
250	395	Lime & Shale brks.
395	415	Shale
415	450	Shale & Lime
450	475	Lime
475	560	Shale & Lime brks.
560	650	Lime & Shale
650	760	Shale & Lime strks.
760	975	Shale & Shells
975	1145	Lime & Shale
1145	1190	Shale & Lime strks.
1190	1250	Lime w/shale brks.
1250	1325	Shale & Shells
1325	1350	Lime w/shale brks.
1350	1510	Lime & Shale
1510	1585	Shale & Lime brks.
1585	1685	Lime & Shale
1685	1865	Shale & Lime strks.
1865	1940	Lime (sandy) w/shale brks.
1940	1990	Shale & Lime strks.
1990	2095	Lime & Shale
2095	2135	Lime
2135	2165	Lime & Shale
2165	2220	Lime
2220	2240	Shale & Lime strks.
2240	2325	Lime & Shale
2325	2430	Lime & Shale strks.
2430	2475	Lime
2475	2560	Shale
2560	2585	Shale & Lime
2585	2700	Shale w/lime strks.
2700	2728	Lime
2728	2855	Lime & Chert
2855	2890	Lime
2890	2925	Lime & Shale
2925	2935	Shale
2935	3000	Shale & Lime
3000	3041	Shale
3041	3054	Viola
3054	3084	Simpson
3084		Total Depth.

RECEIVED

PLUGGING
FILE SEC 3 T 27 R 3E
BOOK PAGE 66 LINE 36

Well Log - Kiser #1
Page 2


I hereby certify that the foregoing is a true and correct copy of the Well Log for the Kiser #1 well drilled for Mr. J. P. Gaty and completed April 30, 1953.

MORRISON DRILLING COMPANY, INC.


C. W. Wilson - Secretary-Treasurer

STATE OF KANSAS)
) ss.
COUNTY OF BUTLER)

SUBSCRIBED AND SWORN TO, Before the Undersigned, a Notary Public, in and for the County and State aforesaid this 5th day of May, 1953.


Notary Public

My Commission Expires January 10, 1955.

[Faint, illegible handwritten text]