


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Butler County, Sec. 5 Twp. 27S Rge. 3 (E) ~~(W)~~

Location as "NE/CNW&SW" or footage from lines NE/4 SE/4 NE/4  
Lease Owner Mr. J. P. Gaty  
Lease Name James Well No. 1  
Office Address 11 Cypress Drive, Forrest Hills, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 21 1954  
Application for plugging filed (Verbal) July 21 1954  
Application for plugging approved (Verbal) July 21 1954  
Plugging commenced July 21 1954  
Plugging completed July 21 1954  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes 1

Name of Conservation Agent who supervised plugging of this well Lawrence W. Matthews, Jr.  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3240 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged hole with rotary mud to 155' - Cemented  
W/10 Sacks Dry Cement on Wood Plug. Filled Hole  
W/Rotary Mud to 20' Base of Cellar, Solid Bridge  
& Cemented W/5 Sacks Mixed Cement.

RECEIVED  
STATE CORPORATION COMMISSION  
7/28/54


CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Morrison Drilling Company, Inc.  
Address Drawer 712, El Dorado, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
John P. Gaty (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John P. Gaty  
11 Cypress Dr., Wichita, Ks. (Address)

SUBSCRIBED AND SWORN to before me this 27 th day of July, 1954  
My commission expires Dec. 12, 1955  
My commission expires \_\_\_\_\_  
J. Arnold Dowd Notary Public.



PLUGGING  
FILED SEC 5 T 27 R 3E  
BOOK PAGE 51 LINE 35

WELL LOG - JAMES #1

OPERATOR: Mr. J. P. Gaty  
11 Cypress Drive  
Forrest Hills  
Wichita, Kansas

LOCATION: NE/4 SE/4 NE/4  
Section 5-278-3E  
Butler County, Kansas

PRODUCTION: D & A

CONTRACTOR: Morrison Drilling Company, Inc.  
Drawer 712  
El Dorado, Kansas

Farm: James - Well #1  
Date Commenced: July 9, 1954  
Date Completed: July 21, 1954

Total Depth: 3240' - Rotary

From	To	Formation
0	103	Cement
103	110	Open Hole
110	320	Lime and shale
320	430	Lime and shale
430	445	Red Bed
445	460	Lime and shale streaks
460	525	Shale and lime streaks
525	570	Sand and shale
570	790	Lime and shale
790	1130	Shale and lime streaks
1130	1195	Lime and shale
1195	1295	Shale and lime streaks
1295	1375	Lime
1375	1430	Lime and shale streaks
1430	1765	Lime and shale
1765	1965	Shale and lime
1965	2050	Lime and shale
2050	2175	Lime and shale streaks
2175	2250	Shale and lime streaks
2250	2341	Lime and shale
2341	2493	Lime
2493	2627	Lime and shale
2627	2765	Shale and lime
2765	2781	Lime and chert
2781	2789	Sandy shale
2789	2797	Shale
2797	2837	Lime
2837	2959	Lime and chert
2959	3043	Lime
3043	3079	Lime and shale
3079	3129	Shale
3129	3143	Lime - Dol.
3143	3157	Simpson - Dol.
3157	3169	Sandy Dol.
3169	3179	Simpson Sand
3179	3223	Sand and shale
3223	3240	Arbuckle
3240		Total Depth

I hereby certify that the foregoing is a true and correct copy of the Well Log for the James #1 well drilled for Mr. J. P. Gaty, and completed July 21, 1954.

MORRISON DRILLING COMPANY, INC.

  
C. W. Wilson - Secretary-Treasurer

WELLS LOG  
FILE SEC 5 T 27 R 3E  
BOOK PAGE 57 LINE 35

Page -2- Well Log - James Well #1

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF BUTLER )

SUBSCRIBED AND SWORN TO, Before the Undersigned, a Notary Public,  
in and for County and State aforesaid this 22nd. day of July, 1954.



*Wm. D. ...*  
\_\_\_\_\_  
Notary Public

My Commission Expires January 10, 1955.