

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: R & B Oil & Gas, Inc.
 Address: PO Box 195, Attica, KS 67009
 Phone: (620) 254-7251 Operator License #: 31191
 Type of Well: Oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: _____ (Date)
 by: Doug Louis (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Kansas City Depth to Top: 3654 Bottom: 3658 T.D. 3925
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-077-00112-00-01
 Lease Name: Jones
 Well Number: 1 OWWO
 Spot Location (QQQQ): _____ - SW - SE - SW
330 Feet from North / South Section Line
3630 Feet from East / West Section Line
 Sec. 25 Twp. 31 S. R. 6 East West
 County: Harper
 Date Well Completed: 12-10-07
 Plugging Commenced: 2-13-08
 Plugging Completed: 2-15-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	531	
Kansas City	Oil	3654	3658	5 1/2	3787	2880

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Sand at 3570', bailed 5 sacks cement, ripped casing at 3020', worked pipe, ripped casing at 2880', pipe came free, pulled casing up to 1050', pumped 35 sacks & 100# hulls at 1050', pulled up to 580', pumped 35 sacks & 100# hulls, pulled up to 250', circulated with 80 sacks to surface, pulled rest of casing.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
 Address: 190 US Highway 56, Ellinwood, KS 67526
 Name of Party Responsible for Plugging Fees: R & B Oil & Gas, Inc.
 State of Kansas County, Harper, ss.

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 20 2008

Randy Newberry (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Randy Newberry
 (Address) PO Box 195, Attica, KS 67009

SUBSCRIBED and SWORN TO before me this 19th day of March, 2008
Jane Swingle My Commission Expires: 1-6-2011
 Notary Public, Jane Swingle

QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 1788

Date	2-15-08	Sec.	25	Twp.	31	Range	6	Called Out		On Location		Job Start		Finish		
Lease	Jones	Well No.	10WWD			Location	SE 2N 1 1/2 E of Harper			Harper County	KS State					
Contractor	Quality well service							Owner	Harper							
Type Job	Plug							To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.								
Hole Size								T.D.								
Csg.	5 1/2							Depth	Charge To R + B Oil + Gas							
Tbg. Size								Depth	Street							
Drill Pipe								Depth	City State							
Tool								Depth	The above was done to satisfaction and supervision of owner agent or contractor.							
Cement Left in Csg.								Shoe Joint								
Press Max.								Minimum								
Meas Line								Displace								
Perf.								CEMENT								
EQUIPMENT								Amount Ordered	150 sks 60/40 4%							
Pumptrk	6	No.	Cementer David		Helper		Consisting of									
Bulktrk	4	No.	Driver Rich		Driver		Common	90 @ 12.00				1080.00				
Bulktrk		No.	Driver		Driver		Poz. Mix	60 @ 6.50				390.00				
JOB SERVICES & REMARKS								Gel.	6 @ 18.00				108.00			
Pumptrk Charge	PTA		700.00		Chloride											
Mileage	45	@ 6.00		270.00		Hulls	200 # @ 25.00				50.00					
Footage								Salt								
Total							970.00	Flowseal								
Remarks:	1st 35 sks 100# Hulls @ 10.50															
								Sales Tax								
2nd 35 sks 100# Hulls @ 5.80								Handling	158 @ 2.00				316.00			
3rd 80 sks circulated to surface								Mileage	80 per sk per mile				568.80			
								PUMP TRUCK CHARGE				Sub Total 970.00				
												Total				
								Floating Equipment & Plugs								
								Squeeze Manifold								
Used 150 sks								Rotating Head								
													Tax 184.59			
													Discount (348.00)			
Signature David Brady													Total Charge 3319.39			

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 20 2008
CONSERVATION DIVISION
WICHITA, KS