

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Novy Oil & Gas, Inc.
 Address: 125 North Market Suite #1230
 Phone: (316) 265-4651 Operator License #: 31714
 Type of Well: Oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 12-27-2007 (Date)
 by: Steve Bond (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Arbuckel Depth to Top: 3361 Bottom: 3370 T.D. 3370
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 00921077 - 00-00
 Lease Name: Scheweis
 Well Number: 1
 Spot Location (QQQQ): SE - NW - NE -
990 Feet from North / South Section Line
1650 Feet from East / West Section Line
 Sec. 35 Twp. 17 S. R. 12 East West
 County: Barton
 Date Well Completed: 11-11-1976
 Plugging Commenced: 3/11/2007
 Plugging Completed: 03/12/2008

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	Water	Surf	273	8 5/8	273	0
Arbuckel	oil & water	Surf	3361	5 1/2	3361	0
		Surf	2124	2 7/8	3300	1176

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rigged up Log Tech Tag top of sub pump at 2124 perf tubing at 2123 Rig up Copeland Acid Mix and pump 330 Sacks of 60/40 Poz with 4% gel. didn't Circulate to surface pump 12 BBL water SDFN Pressured TBG to 2000 Held Pressured 4 1/2 to 800 Held. Perf TBG at 904 Held 800 PSI. Perf 400 Feet held 800 PSI. Run 210 Ft 1In. between 2 7/8 and 4 1/2 pumped 30 sacks of 60/40 POZ With 4 % Gel Circulated to surface. Rig down Copeland Acid. Cut off well Head well plugged.

Name of Plugging Contractor: Novy Oil & Gas, Inc. mikes testing & salvage inc 31529 License #: 31714
 Address: 125 N. Market #1230 Wichita, Kansas 67202

Name of Party Responsible for Plugging Fees: Novy Oil & Gas, Inc.
 State of Kansas County, Sedwick, ss.
 Michael E. Novy (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Michael E. Novy
 (Address) 125 N. Market #1230 Wichita, Ks 67202

SUBSCRIBER and SWORN TO before me this 1 ST day of April 20 08
Connie L. Crook My Commission Expires: 12-12-2008
 Notary Public

KCC PKT
 RECEIVED
 KANSAS CORPORATION COMMISSION
 APR 04 2008
 CONSERVATION DIVISION
 WICHITA, KS