

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION
Address: 1700 Waterfront Parkway, Bldg. 500 Wichita, KS 67206
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: verbal (Date)
by: Pat Staab (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All. (If needed attach another sheet)
Arbuckle Depth to Top: 3551 Bottom: 3554 T.D. 3665

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-22208-00-00
Lease Name: McCord A
Well Number: 18
Spot Location (QQQQ): _____ - NE - SE - SE
890 Feet from North / South Section Line
280 Feet from East / West Section Line
Sec. 26 Twp. 11S S. R. 17W East West
County: Ellis
Date Well Completed: 3/81
Plugging Commenced: 3/26/08
Plugging Completed: 3/26/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	328'	-----
				5-1/2	3664'	-----
				DV	1277'	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


MIRU to Plug and Abandon. TIH w/tbg to 3317'. Spotted 60 sx 60/40 poz w/4% gel and 300# hulls w/12
sx gel on top. Pulled tubing to 1850'. Circulated cement to surface - 185 sx w/250# hulls. TOH w/tubing.
Connected to 8 5/8" and pumped 50 sx cement. SIP - 150#. Connected to 5 1/2" and pumped 30 sx. SIP - 400#. Total of 325 sx cement

Approved by Pat Staab w/KCC.
Name of Plugging Contractor: Smoky Hills Well Service License #: 32452
Allied Cementing Co., Inc.
Address: P.O. Box 31, Russell, KS 67665-0031
Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Sedgwick, ss.
Pat Canaday (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

RECEIVED
KANSAS CORPORATION COMMISSION
APR 18 2008
CONSERVATION DIVISION
WICHITA, KS

(Signature) Pat Canaday
(Address) 1700 Waterfront Parkway, bldg. 500 Wichita, KS 67206

SUBSCRIBED and SWORN TO before me this 17th day of April 20 08
Michelle D. Henning My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials