

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

2-050579

15-173-20362-00-01

7-19

API NUMBER: DOCKET #D-20,310

SENESE

~~C E/2 NE SE~~, SECTION 36 TOWNSHIP 27 RANGE 2E

OPERATOR LICENSE # 7216
OPERATOR OIL TECH PRODUCERS CORP.
NAME & P.O. BOX 740
ADDRESS MOUNDRIDGE, KS 67107

KCC 1650
ZAP 430 -330
1980

FEET FROM S SECTION LINE
FEET FROM E SECTION LINE

LEASE NAME: ^{KCC ZAP} F.D. STURDEVANT #1
COUNTY: SEDGWICK
WELL TOTAL DEPTH: 3285' 106,76
PIPE: 4 1/2" @ 3207'
SURFACE CASING: 8 5/8" @ 200'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD X D&A _____
DOCKET #D-20,310

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SAGE OIL COMPANY
ADDRESS: P.O. BOX 12, VIRGIL, KS 66870 LICENSE: 5684

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 18 MONTH: 7 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: DISTRICT II
COMPANY NAME: OIL TECH PRODUCERS CORPORATION PHONE: (316) 678-3440
WERE: SAND BACK AND SPOT 5 SACKS OF CEMENT AT 3080'. SHOOT 4 1/2" CASING AT 2216' AND PULL UP TO 250'. CIRCULATE CEMENT FROM 250' TO SURFACE. PULL CASING OUT OF HOLE AND TOP OFF WITH CEMENT.

PLUGGING PROPOSAL RECEIVED BY: GEORGE SAGE

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 16:30 DAY: 19 MONTH: 7 YEAR: 1996

ACTUAL PLUGGING REPORT: SANDED BACK AND SPOTTED 5 SACKS OF CEMENT AT 3080'. SHOT 4 1/2" CASING AT 2216'. PULLED CASING UP TO 250' AND CIRCULATED CEMENT SLURRY TO SURFACE. PULLED CASING OUT OF HOLE AND TOPPED OFF WITH CEMENT.

RECEIVED
KANSAS CORPORATION COMMISSION
9/5/96
SEP 05 1996

REMARKS: 120 SACKS OF CEMENT SLURRY
CONSERVATION DIVISION
WICHITA KS

INVOICED

DATE SEP 05 1996

INV. NO. 46423

7-19

I DID OBSERVE THIS PLUGGING.

JERRY CLARK

FORM CP-2/3
REV. 7/96