

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

15-173-20118-00-00

7-10

API NUMBER: 15- NA

C W/2 SE SE , SECTION 36 TOWNSHIP 27 RANGE 2E

OPERATOR LICENSE # 7216 660 FEET FROM S SECTION LINE  
OPERATOR OIL TECH PRODUCERS CORP. 990 FEET FROM E SECTION LINE  
NAME & ADDRESS PO BOX 740, 139 S CHRISTIAN AVE  
MOUNDRIDGE, KS 67107  
LEASE NAME: C. PRAY #1-A  
COUNTY: SEDGWICK  
WELL TOTAL DEPTH: 3155' 102.53  
PIPE: 4 1/2" @ 3141'  
SURFACE CASING: 8 5/8" @ 206'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: SAGE OIL COMPANY  
ADDRESS: PO BOX 12, VIRGIL, KS 66870 LICENSE: 5684

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 10 MONTH: 7 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: DISTRICT II  
COMPANY NAME: SAGE OIL COMPANY PHONE: (316) 678-3440  
WERE: SAND BACK AND SPOT 5 SACKS OF CEMENT AT 2730'. SHOOT 4 1/2" CASING AT 2000' AND PULL UP TO 250'. CIRCULATE CEMENT FROM 250' TO SURFACE. PULL CASING OUT OF HOLE AND TOP OFF WITH CEMENT.

PLUGGING PROPOSAL RECEIVED BY: GEORGE SAGE

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( ) PART ( X ) NONE ( )

COMPLETED: HOUR: 15:00 DAY: 10 MONTH: 7 YEAR: 1996

ACTUAL PLUGGING REPORT: SANDED BACK AND SPOTTED 5 SACKS OF CEMENT AT 2730'. SHOT 4 1/2" CASING AT 1561' AND PULLED UP TO 250'. CIRCULATED CEMENT FROM 250' TO SURFACE. PULLED CASING OUT OF HOLE AND TOPPED OFF WITH CEMENT.

RECEIVED  
KANSAS CORPORATION COMMISSION

9/5/96  
SEP 05 1996

REMARKS: 80 SACKS OF CEMENT SLURRY

CONSERVATION DIVISION  
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

JERRY CLARK

INVOICED  
SEP 05 1996

DATE  
INV. NO. 46422

7-10