

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20804-00-00
Spot: SWNE Sec/Twnshp/Rge: 8-35S-36W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease Name: BANES Well #: 1
County: STEVENS Total Vertical Depth: 7000 feet

Operator License No.: 6677
Op Name: SANDLIN OIL CORPORATION
Address: 621 17TH ST STE 2055
DENVER, CO 80293

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2200		WITH 2 SX CMT
CIBP		6520		WITH 2 SX CMT 227.50
PROD 5.5		6997	0	WITH 1230 SX CMT
SURF 9.625		1800		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/10/2008 3:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GILBERT PAYNE Company: SANDLIN OIL CORP. Phone: (303) 292-3313

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/10/2008 4:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

RAN CEMENT BOND LOG. GOOD CMT FROM 600' TO 2200'. CIBP @ 6520' WITH 2 SX CMT. CIBP @ 2200' WITH 2 SX CMT. PERFORATE 5 1/2" @ 600'. CIRCULATED CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
6796	6798		
6584	6594		

INVOICED

DATE 4-25-08

INV. NO. 2008061618

RECEIVED
KANSAS CORPORATION COMMISSION


APR 16 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Jack MacLaskey
(TECHNICIAN)