

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23704-00-00  
Spot: E2W2 Sec/Twnshp/Rge: 33-7S-20W  
2640 feet from S Section Line, 1980 feet from W Section Line  
Lease Name: BBR UNIT Well #: 1  
County: ROOKS Total Vertical Depth: 3505 feet

Operator License No.: 31569  
Op Name: BACH, JASON DBA BACH OIL PRODUC  
Address: PO BOX 723  
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218		

113.91

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/25/2008 12:00 PM  
Plug Co. License No.: 33237 Plug Co. Name: ANDERSON, C. D. DBA ANDERSON DRILLING  
Proposal Rcvd. from: LARRY BRUNGARDT Company: BACH OIL PRODUCTION Phone: (308) 928-8920

Proposed Plugging Method: Ordered 215 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE  
Date/Time Plugging Completed: 03/25/2008 2:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 3480' w/25 sxs.  
2nd. Plug at 1600' w/25 sxs.  
3rd. Plug at 914' w/100 sxs.  
4th. Plug at 268' w/40' sxs.  
5th. Plug at 40' w/10'sxs.  
Rathole with 15 sxs.

Perfs:

INVOICED  
DATE 4-24-08  
INV. NO. 2008061604

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 22 2008


CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

APR 21 2008

