

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23712-00-00  
Spot: NWNWSE Sec/Twnshp/Rge: 23-9S-19W  
2275 feet from S Section Line, 2550 feet from E Section Line  
Lease Name: STAHL 'B' Well #: 1  
County: ROOKS Total Vertical Depth: 3421 feet

Operator License No.: 6931  
Op Name: BOWMAN OIL COMPANY, A GENERAL  
Address: 805 CODELL RD  
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	258		

111.18

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/18/2008 1:00 AM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: BILL WYNN Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed Plugging Method: Ordered 215 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE  
Date/Time Plugging Completed: 04/18/2008 6:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 3015' w/25 sxs.  
2nd. Plug at 1513' w/25 sxs.  
3rd. Plug at 865' w/100 sxs.  
4th. Plug at 258' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.

Note: Left 13 drill collars in the hole. TOF 3015'.

Perfs:

**INVOICED**  
DATE 4-24-08  
INV. NO. 2008061607

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 21 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CM

APR 18 2008

