

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22237-00-00
Spot: NWENW Sec/Twnshp/Rge: 29-13S-21W
330 feet from N Section Line, 1760 feet from W Section Line
Lease Name: HONAS Well #: 1-29
County: TREGO Total Vertical Depth: 4250 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1766		
PROD	5.5	4240	0	150sx
SURF	8.625	223	0	150sx

138.13

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/15/2008 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 257-2719

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 14 sxs gel - 800# hulls.
DV Tool at 1766' w/180 sxs.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/15/2008 2:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Backside pressured to 200# with one bbl of water.
Hooked to 5 1/2" casing and pumped 60 sxs 60/40 pozmix - 4% gel and 300# hulls - followed with 14 sxs gel spacer.
Pumped 250 sxs 60/40 pozmix - 4% gel with 500# hulls.
S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
4093	4097		
4075	4079		
3898	3904		
3855	3858		
3722	3725		

INVOICED

DATE 4-24-08
INV. NO. 2008061608

RECEIVED
KANSAS CORPORATION COMMISSION

APR 21 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALILTY OIL WELL CEMENTING.

Plugged through: CSG

District: 04

Signed Pat Bedore

(TECHNICIAN)

CM

APR 17 2008

[Handwritten signature]

DOWNING-NELSON OIL CO
HAYS KS 67601

29-13S-21W
110' E, C NW NE NW

#1-29 HONAS

site 2 S & 6 W OF ELLIS KS
contr: DISCOVERY DRILLING #1
opd: RON NELSON

city: TREGO
field: RIGA SOUTH EXT (5/8 W;
INFLD DISC)

API 15-195-22237

fr date 07/22/2003 spd date 09/24/2003 drg comp 09/30/2003 card issued 04/19/2004 last revised 04/19/2004

E.V: 2366 KB, 2358 GL LOG
tops.....depth/datum
ANH.....1772 +594
B/ANH.....1816 +550
TOP.....3455 -1089
HEEB.....3686 -1320
TOR.....3705 -1339
LANS.....3721 -1355
BKC.....3964 -1598
MARF.....4066 -1700
CONG.....4160 -1794
ARB.....4195 -1829
RTD.....4250 -1884

IP status
OIL, P 60 BOPD, NW, LKC 3998-3904, 11/01/2003
CSG: 8-5/8" 223.56 / 150 SX (ALT 2), 5-1/2" 4240.18 / 150 SX,
DV TOOL AT 1766 / 180 SX
NO CORES
DSTS TAKEN - DETAILS NA
TRGT ZN: LKC, CHER (OIL), PTD 4100 (CHER), MICT - CO,
PF (LKC) 3998-3904, W / 4 SFF, AC 500 GAL (MCA), SWB LD,
RE-AC 1500 GAL (15% NE), SWB LD, GSO, POP, P 70 BQ/24
HRS, IPP 60 BOPD, NW, NSG (GR 24), DOFP 11/1/2003 - NO
OTHER INFO AVAILABLE - TEMP COMP 4/19/2004

COPYRIGHT 2004
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS