

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-30514-00-01
Spot: W2SESE Sec/Twnshp/Rge: 22-14S-14W
660 feet from S Section Line, 990 feet from E Section Line
Lease Name: BOXBERGER G A Well #: 2
County: RUSSELL Total Vertical Depth: 3066 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	8	2965	0	w/250 sxs cmt
SURF	10.75	420	0	w/480 sxs cmt

\$ 99.65

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/20/2008 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: TERRY MORRIS Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-1307

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/20/2008 5:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 800' - 450' - 200'.
Ran 2300' tubing - pumped 10 sxs gel - pumped 50 sxs 60/40 pozmix - 4% gel cement.
Pulled to 800' - circulated with 85 sxs cement.
POOH. Tied onto casing and pumped 90 sxs cement.
Cement circulated up backside.

Perfs:

Top	Bot	Thru	Comments
3052	3059		

INVOICED
DATE 3-14-08
INV. NO. 2008061530

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: QUALITY CEMENTING COMPANY.

Plugged through: CSG

MAR 27 2008

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed *Case Morris*
(TECHNICIAN) *cm*

MAR 25 2008

Handwritten signature

