

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20802-00-06
Spot: SWNENW Sec/Twnshp/Rge: 34-14S-14W
4298 feet from S Section Line, 3719 feet from E Section Line
Lease Name: LOUIE A Well #: 1
County: RUSSELL Total Vertical Depth: 3249 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE STE 740 LB 30
DALLAS, TX 75205

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3145		
PROD	5.5	3249	2100	150 SX
SURF	8.625	443	0	325 SX

105.59

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/25/2008 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. Phone: (785) 483-2169

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel - 500# hulls.
CIBP at 3145'. Sand at 2910' w/5 sxs.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/25/2008 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Sanded to 2910' - dumped 5 sxs cement. Cut casing at 2100'.
Pulled casing to 1450' - pumped 100 sxs cement with 300# hulls.
Pulled casing to 800' - pumped 35 sxs cement with 100# hulls.
Pulled casing to 500' - pumped 30 sxs cement with 100# hulls.
Pulled casing to 250' - circulated cement with 50 sxs - hole full.

Perfs:

Top	Bot	Thru	Comments
3056	3060		
2995	2998		
2985	2985		

INVOICED
DATE 4-10-08
INV. NO. 2008061511

RECEIVED
KANSAS CORPORATION COMMISSION

APR 02 2008

Remarks: QUALITY CEMENTING COMPANY-TICKET #1822.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 04

Signed

Marvin Mills

(TECHNICIAN)

CM

Form CP-2/3

MAR 31 2008

LOUIS M. HALL OPERATIONS

#1 LOUIE "A"

34-14-14N
SW NE NW

BOX 33, RUSSELL, KS.

CTY. RUSSELL

CONTR. DUKE DRILLING CO.

GEOLOG. FRANCIS WHISLER

FIELD HALL-GURNEY

E 1731 KB c41/17/75 3/18/76

P 30 BOPD + 5% WTR
LKC 2961-2998

API 15-167-20,802

LOG	TOPS	DEPTH	DATUM
AND		759	+1022
GR SAV		2326	- 535
DRY SH		2335	- 544
DOVER LS		2350	- 559
LANGDON		2354	- 563
TARK		2396	- 605
WILLARD		2417	- 626
ELM		2458	- 667
HOW		2600	- 809
TOP		2656	- 875
HEER		2898	-1107
TOP		2916	-1125
LKC		2959	-1168
EXC		3150	-1359
GR W		3275	-1484
TOP		3250	-1459

INDEPENDENT OIL & GAS SERVICE
P.O. BOX 100, RUSSELL, KANSAS

3 5/8" 443/325SX, 5 1/2" 3249/150SX
 DST (1) 2954-90/30-30-60-60, 90' GIP,
 150' O&GCM, SIP 704-760#, FP 49-
 56#, 73-81#
 DST (2) 2986-3010/30-60-60-60, 120' GIP,
 65' VSQCM+SFO, SIP 179-114#, FP
 65-81#
 DST (3) 3049-3059/30-60-60-60, 300' GIP,
 60' O&GCM, 120' MW, SIP 809-775#,
 FP 32-89#
 DST (4) 3189-3227/30-30-30-30, 120'
 OCM, SIP 1050-993#, FP 55-81#
 MICT - PF (GR W) 3222-25, A 500, REC
 LD, SWB 7 BOPH, TR W, BP @ 3150, PF
 (LKC) 2951-64, 2966-59, 2982-85, 2995-
 98, A 4000, REC LD, SWB 7 BOPH, 90%
 OIL