

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-057-0014-00-01  
Spot: NESE Sec/Twnshp/Rge: 10-25S-21W  
1980 feet from S Section Line, 660 feet from E Section Line  
Lease Name: MCKEE OWWO Well #: 2  
County: FORD Total Vertical Depth: 4430 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1700		CMT TO SURFACE
PROD	4.5	4380	0	WITH 175 SX CMT
SURF	8.625	253		WITH 225 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/01/2007 9:45 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: FLIP PHILLIPS Company: PINTAIL PETROLEUM Phone: (316) 263-2243

Proposed Plugging Method: SAND TO 4100' & 4 SX CMT. RUN TBG TO 1700'. LOAD HOLE & 25 SX CMT. PULL TO 720', CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/01/2007 11:10 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

\*\*DV TOOL @ 1700', CEMENTED TO SURFACE.\*\* SAND TO 4100' WITH 4 SX CMT. 1ST PLUG AT 1700' WITH 25 SX CMT & 50# HULLS. 2ND PLUG AT 720' WITH 60 SX CMT. LOST CIRCULATION. 11/2/07: TOPPED OFF WITH 65 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4150	4152		


**INVOICED**  
DATE 11-30-07  
INV. NO. 2008060829

**RECEIVED**  
NOV 1 2007  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01



Signed Eric MacLaren  
(TECHNICIAN)

PKS