

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19244-00-~~00~~ ^{at KCC ap}
Spot: SESWSW Sec/Twnshp/Rge: 4-15S-12W
364 feet from S Section Line, 4111 feet from E Section Line
Lease Name: SMOKEY UNIT Well #: TR2-W3
County: RUSSELL Total Vertical Depth: 3272 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment	
PROD	5.5	3263	0	w/150 sxs cmt	\$106.34
SURF	10	764	0	w/unknown sxs cmt	

Well Type: EOR UIC Docket No: E16068.5 Date/Time to Plug: 03/26/2007 8:30 AM
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.
Proposal Rcvd. from: VAL DREHER Company: FARMER, JOHN O., INC. Phone: (785) 483-3144

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/26/2007 12:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 995' and 1450'.
Ran tubing to 3000'.
Pumped 125 sxs 60/40 pozmix - 10% gel cement with 500# hulls.
Pulled to 1500' - circulated with 250 sxs cement with 300# hulls.
POOH. Pumped 110 sxs cement down casing.
Cement circulated up backside.

Perfs:

INVOICED
DATE 5-1-07
INV. NO. 2007061677

RECEIVED
KANSAS CORPORATION COMMISSION
APR 26 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY CEMENTING COMPANY.

Plugged through: TBG

District: 04

TD

Signed Case Morris
(TECHNICIAN)

APR 12 2007

PK