

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19730-00-00
Spot: NWSENW Sec/Twnshp/Rge: 21-26S-5E
3620 feet from S Section Line, 3787 feet from E Section Line
Lease Name: KOGLER Well #: 76
County: BUTLER Total Vertical Depth: 2553 feet

Operator License No.: 32979
Op Name: DUNNE INVESTMENTS OPERATING, I
Address: 8100 E 22ND ST N # 1100
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.188	2509		45 SX
SURF	8.625	831		

82.97

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: GARY LARUE Company: DUNN INVESTMENTS OPERATING Phone: (316) 684-6508

Proposed Plugging Method: PER KCC REGULATIONS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/19/2008 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 1458', COULD NOT GET TO TD, LAYED DOWN TUBING. SHOT PERFORATIONS @ 1420', RIH W/TBG & PACKER. CONSOLIDATED MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL. LAYED DOWN TUBING. 2-19-2008, RIH W/TBG @ 310', CONSOLIDATED MIXED & PUMPED 90 SXS 60/40 POZMIX 4% GEL TO SURFACE. SWEDGED INTO CASING AND PUMPED 10 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 12:00, 2-19-2008, CONSOLIDATED TICKET #12942.

Perfs:

Top	Bot	Thru	Comments
2589	2628		
2517	2538		
2482	2508		

INVOICED
DATE 4-14-08
INV. NO. 200806153

RECEIVED
KANSAS CORPORATION COMMISSION


APR 07 2008

Remarks: BRIDGE PLUG @ 2510

Plugged through: TBG

District: 02

Signed _____



(TECHNICIAN)

CONSERVATION DIVISION
WICHITA, KS

