

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19731-00-00
Spot: SWSENW Sec/Twnshp/Rge: 21-26S-5E
2975 feet from S Section Line, 3751 feet from E Section Line
Lease Name: KOGLER Well #: 77
County: BUTLER Total Vertical Depth: 2519 feet

Operator License No.: 32979
Op Name: DUNNE INVESTMENTS OPERATING, I
Address: 8100 E 22ND ST N # 1100
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2530		30 SX
SURF	8.625	1190		

81-87

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: GARY LARUE Company: DUNN INVESTMENTS OPERATING Phone: (316) 684-6508

Proposed
Plugging
Method:

PER KCC REGULATIONS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 02/19/2008 2:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 930', COULD NOT GET TO TD, COLLAPSED CASING. LAYED DOWN TUBING. SHOT SPERFORATIONS @ 900'-930', RIH W/TBG & PACKER, CONSOLIDATED MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL. LAYED DOWN TUBING. 2-19-2008, RIH W/TBG @ 310', CONSOLIDATED MIXED & PUMPED 45 SXS 60/40 POZMIX 4% GEL TO SURFACE. SWEDGED INTO CASING AND PUMPED 5 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 2:30, 2-19-2008, CONSOLIDATED CEMENT TICKET #12942.

Perfs:

Top	Bot	Thru	Comments
2535	2547		
2494	2497		

INVOICED
DATE 4-14-08
INV. NO. 2008001531

RECEIVED
KANSAS CORPORATION COMMISSION

APR 07 2008


Remarks: CONSOLIDATED CEMENT TICKET #12942.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

PKJ