

4-041982

15-163-11872-00-00

9-11

TO
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1951

SE SE SE /4 SEC. 06 , 10 S, 20 W
330 feet from S section line
330 feet from E section line

Operator license# 5363
Operator: Berexco, Inc.
Address: P.O. Box 723
Hays, Kansas 67601

Lease: Tucker Well # 1
County: Rooks 125.58
Well total depth 3864 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 159 Feet
W/120 sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 11:00 A.M. Day: 11 Month: September Year 1998

Plugging proposal received from: Bob Grant

Company: Berexco, Inc. Phone: 785-628-6101

Were: 5 1/2" casing set at 3848' w/125 sxs cement. Perf. At 3618' - 3736'.
Lockset 3610'. Squeeze at 1550' w/375 sxs. Solid bridge @ 1750'.
Ordered 200 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 1:30 P.M., Day 11, Month: September, Year: 1998

Actual plugging report: R.I.H. with tubing to 1725' - spotted 120 sxs cement with 500# hulls to circulate at surface. P.O.O.H. with tubing and squeezed casing with 50 sxs cement. Max. P.S.I. 800#.
Squeezed 8 5/8" S.P. with 25 sxs cement. Max. P.S.I. 600#.

Remarks:
Condition of casing(in hole): GOOD BAD X Any plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING X CASING Elevation: G.L.

I did[X] / did not[] observe the plugging.

Dennis L. Hamel
(agent)

RECEIVED
SEP 30 1998
FORM CP-2/3

KANSAS CORPORATION COMMISSION

SEP 30 1998

INVOICED

DATE SEP 30 1998
INV. NO. 51386

09/03/1998