

To: 6 050018  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-25  
API NUMBER 15- 163-23,009-00-00  
C NE SE 6 10 20  
SEC. , T S, R W/Ex  
1980 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5652  
Operator: Mustang Co. Inc.  
Name & Address Highway 281 So. Drawer 1609  
Great Bend, Ks. 67530

Lease Name Hinkhouse Well # 7  
County Rooks 127.73  
Well Total Depth 3930 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 217

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Mallard Drilling Co. Inc. License Number

Address

Company to plug at: Hour: AM Day: 25 Month: Oct Year: 19 88

Plugging proposal received from Gary

(company name) Mallard Drilling (phone)

were: Order 230 sks 60/40 Poz 6% Gel 3% Cal Cl 1 sk F.C. and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by Bruce D. Basye  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations C 3:30AM Day: 25 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT  
1st plug at 3800' w/25 sks . Arb.  
2nd plug at 1770' w/25 sks Anhy  
3rd plug at 1000' w/100 sks 1 sk F.C. - Dakota  
4th plug at 270' w/40 sks  
5th plug at 40' w/10 sks  
15 sks in rathole 15 sks in mousehole

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 21 1988  
11-21-1988  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Allied Cement.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I (did / did not) observe this plugging.

Signed Bruce D. Basye  
(TECHNICIAN)  
Bruce D. Basye

DATE 11-29-88  
INV. NO. 23155