

4-041866

15-163-02041-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

12-9

API Number: 15- - 5-5-50

SE SE SE /4 SEC. 10 , 10 S, 20 W  
330 feet from S section line  
330 feet from E section line

Operator license# 5030

Lease: Hinkhouse Well # 2

Operator: Vess Oil Corporation

County: Rocks 123,43

Address: 8100 E. 22nd. St. N. Bldg 300  
Wichita, Kansas 67226

Well total depth 3798 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 250 feet  
w/ 165 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing, Inc. License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 9 Month: December Year 1996

Plugging proposal received from: Joel Stull

Company: Vess Oil Corporation Phone: 913-885-4352

Were: 5 1/2" casing set at 3771' w/125 sxs.  
W.L.M. 3798'. O.H. 3771' - 3798'. P.B.T.D 3798'. 5 1/2" casing squeezed at 910' w/500 sxs -  
1400' w/130 sxs.  
Ordered 275 sxs 60/40 pozmix - 10% gel with 1/4# F.C. - 500# hulls - 13 sxs gel.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 10:45 A.M., Day: 9, Month: December, Year: 1996

Actual plugging report: 5 1/2" casing - pumped as follows: 50 sxs w/300# hulls, followed with  
13 sxs gel, followed with 170 sxs with 200# hulls. Max. P.S.I. 500#. S.I.P. 200#. 8 5/8"  
S.P. - 55 sxs cement. Max. P.S.I. 500#.

12-30-1996  
Dennis L. Hamel  
12-30-1996

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING Elevation: 2218 K.B.

I did [ X ] / did not [ ] observe the plugging.

Dennis L. Hamel  
(agent)

Form CP-2/3

INVOICED

DATE JAN 03 1997

INV. NO. 47257

12-9