

9-30

307
R

6-041331

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-02047-00-00

NE SW NE /4 SEC. 10, 10 S, 20 W
3630 feet from S section line
1650 feet from E section line

Operator license# 5048 Lease Sparks well # 2

Operator: Griggs Oil Co. Inc. County Rooks

Address: 107 N. Market Well total depth 3846 feet
Suite 800 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 141 feet

124.99

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 4:00P.M. Day: 30 Month: September Year: 91

Plugging proposal received from: Wilbur Burk

Company: Griggs Oil Co. Phone:

Were: 5 1/2" casing set at 3816' w/125 sks. cement. Perfs. at 3733' to 3737'. Perf. anhy. at 1730'. Perf. base dakota at 1015'. Squeezed @ 1486' w/125 sks. Perf. base of S.P. @ 141'. Ordered 400 sks. 60/40 poz. - 10% gel. w/ 1/4 lb. flocele plus 500 # hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All], Part], None]

Completed: Hour: 6:30P.M., Day: 30, Month: September, Year: 91

Actual plugging report: Pumped in 5 1/2" casing w/20 sks. cement with 1/4 lb. flocele plus pumped in additional 380 sks. cement with 1/4 lb. flocele and 500# hulls mixed in cement. Max. 800 lb. S.I. 400 lb. Release pressure - perf. 141' circulated 60 gpm.

RECEIVED
STATE CORPORATION COMMISSION
OCT 8 1991
10-08-1991
CONSERVATION DIVISION
WICHITA, KS

Remarks:

did not observe the plugging. Dennis L. Hamel

INVOICED

DATE 10-18-91

INV. NO. 33397

Handwritten initials

(agent)
Form CP-2/3