

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20773-00-00  
Spot: S2NENE Sec/Twnshp/Rge: 34-9S-23W  
4290 feet from S Section Line, 660 feet from E Section Line  
Lease Name: LAW B Well #: 6  
County: GRAHAM Total Vertical Depth: 3991 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3991	0	150 SX
SURF	8.625	182	0	150 SX

129.71

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/02/2007 11:00 AM  
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.  
Proposal Rcvd. from: DENNIS KRIMER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 800# hulls.  
Bottom sanded off from TD to 3950' with lock set at 3600'.  
Perf at 1240' - 1950' - 2380'.  
Hole in casing from 2920' to 3367' - not squeezed.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/02/2007 5:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3580' - pumped 65 sxs cement with 300# hulls.  
Pulled tubing to 2585' - pumped 65 sxs cement with 200# hulls.  
Pulled tubing to 1590' - pumped 100 sxs cement with 200# hulls - good circulation of cement.  
Tied on the 4 1/2" casing - squeezed with 35 sxs cement.  
Max. P.S.I. 300#. S.I.P. 250#.  
Tied on the 8 5/8" - squeezed with 60 sxs cement and 100# hulls.  
Max P.S.I. 300#. S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3810	3925		
3659	3663		

**INVOICED**

DATE 11-14-07  
INV. NO. 0008060751

RECEIVED  
KANSAS CORPORATION COMMISSION

NOV 09 2007


CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #24785.

Plugged through: TBG

District: 04

Signed

  
(TECHNICIAN)

Form CP-2/3

NOV 08 2007

