

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-23777-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 32-25S-21E
1155 feet from S Section Line, 2475 feet from E Section Line
Lease Name: SEASTEDT Well #: 3
County: ALLEN Total Vertical Depth: 750 feet

Operator License No.: 33805
Op Name: ENSMINGER OIL, LLC
Address: 1446 3000 ST
MORAN, KS 66755

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2	750	0	
SURF	8	20	0	

35.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/09/2007 11:00 AM
Plug Co. License No.: 33805 Plug Co. Name: ENSMINGER OIL, LLC
Proposal Rcvd. from: DON ENSMINGER Company: ENSMINGER OIL, LLC Phone: (620) 237-4320

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 750' THAT HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/09/2007 12:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 700'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 150'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. ALL 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

INVOICED
DATE 11-14-07
INV. NO. 2008060754

RECEIVED
KCC DISTRICT #3

OCT 24 2007

CHANUTE, KS

CPT

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 08 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: SPOT LOCATION FOR THIS WELL WAS ESTABLISHED VIA GPS AS:2338' WEL & 2495' NSL.

Plugged through: TBG

District: 03

Signed

Clayton P. Titel
(TECHNICIAN)

PPT