

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-23778-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 32-25S-21E
1815 feet from S Section Line, 2475 feet from E Section Line
Lease Name: SEASTEDT Well #: 4
County: ALLEN Total Vertical Depth: 750 feet

Operator License No.: 33805
Op Name: ENSMINGER OIL, LLC
Address: 1446 3000 ST
MORAN, KS 66755

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	20	0	
SURF	2	750	0	<u>35.00</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/09/2007 12:00 PM
Plug Co. License No.: 33805 Plug Co. Name: ENSMINGER OIL, LLC
Proposal Rcvd. from: DON ENSMINGER Company: ENSMINGER OIL, LLC Phone: (620) 237-4320

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 750' THAT HAD BEEN CEMENTED IN AT T.D. ONLY.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 10/09/2007 2:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 675'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND *" ANNULUS TO 150'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

INVOICED
DATE 11-14-07
INV. NO. 2008060754

RECEIVED
KCC DISTRICT #3
OCT 24 2007
CHANUTE, KS
CPT

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 08 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: THE SPOT LOCATION FOR THIS WELL VIA GPS WAS 2021' WEL & 2896' NSL OF S. 32.

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PPT