

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-26267-00-00  
Spot: NENESW Sec/Twnshp/Rge: 32-25S-21E  
2475 feet from S Section Line, 2805 feet from E Section Line  
Lease Name: SEASTEDT Well #: 5  
County: ALLEN Total Vertical Depth: 750 feet

Operator License No.: 33805  
Op Name: ENSMINGER OIL, LLC  
Address: 1446 3000 ST  
MORAN, KS 66755

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2	750	0	
SURF	8.525	20	0	

35.00

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/09/2007 10:00 AM  
Plug Co. License No.: 33805 Plug Co. Name: ENSMINGER OIL, LLC  
Proposal Rcvd. from: DON ENSMINGER Company: ENSMINGER OIL, LLC Phone: (620) 237-4320

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 750' THAT HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/09/2007 11:30 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2' CASING TO 675'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2"&8" ANNULUS TO 150'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

INVOICED  
DATE 11-14-07  
INV. NO. 2008060754

RECEIVED  
KCC DISTRICT #3  
OCT 24 2007  
CHANUTE, KS

CPT

RECEIVED  
KANSAS CORPORATION COMMISSION  
NOV 08 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: SPOT LOCATION ESTABLISHED VIA GPS AS:3123' WEL & 2471' NSL.

Plugged through: TBG

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

PPT