


15-065-02781-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 16 Twp. 8S Rge. (E) 25 (W)
Location as "NE/CNW&SW" or footage from lines NE 1/4 - NE 1/4 - NE 1/4
Lease Owner Champlin Oil & Refining Co.
Lease Name Paxson Well No. 1
Office Address Room 306, Koch Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed December 19 19 54
Application for plugging filed February 16 19 57
Application for plugging approved February 16 (Verbal) 19 57
Plugging commenced 19
Plugging completed - 2-16 - 19 57
Reason for abandonment of well or producing formation Non-Commercial

If a producing well is abandoned, date of last production 2-6 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3920 Feet
Show depth and thickness of all water, oil and gas formations. P.B.T.D.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	214'	None
				5 1/2" OD	3961'	1200'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with crushed rock from 3920' P.B.T.D. to 3850' and dumped 4 sacks of cement on top of rock filling hole from 3850' to 3820' then filled hole with heavy mud to bottom of surface casing and pumped in 80 sacks of cement under pressure filling surface casing from bottom of cellar to bottom of casing.


RECEIVED
STATE CORPORATION COMMISSION
MAR 9 - 1957
CONSERVATION DIVISION
Wichita, Kansas

3/9/57

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Miller Casing Pulling Co.
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]*
Room 306, Koch Bldg., Wichita, Kansas
(Address)



SUBSCRIBED AND SWORN TO before me this 8th day of March 19 57
Cecil J. Yerlesky, Jr. Notary Public.

PLUGGING
FILE SEC 16 T 8 R25W
BOOK PAGE 142 LINE 21

15-065-02781-00-00

CHAMPLIN OIL & REFINING CO.

Paxson #1

NE $\frac{1}{4}$ -NE $\frac{1}{4}$ -NE $\frac{1}{4}$

Sec. 16

Rge. 8S (W) 25

FORMATION RECORD

0 - 30	Surface Dirt
30 - 70	Sand and Gravel
70 - 560	Clay - Shale
560 - 1000	Clay - Shale
1000 - 1060	Shale and Sand
1060 - 1230	Clay and Shale
1230 - 1400	Shale and Shells
1400 - 1560	Shale and Lime Shells
1560 - 1710	Sandy Shale
1710 - 1950	Red Shale
1950 - 2040	Green and Red Shale
2040 - 2120	Red Shale
2120 - 2149	Anhydrite
2149 - 2300	Shale and Shells
2300 - 2390	Gray and Green Shale
2390 - 2530	Broken Lime and Gray Shale
2530 - 2680	Shale and Shells
2680 - 2730	Shale and Lime
2730 - 2880	Shale and Lime Breaks
2880 - 3060	Shale and Lime Shells
3060 - 3080	Lime and Shale
3080 - 3185	Shale and Lime Shells
3185 - 3440	Shale and Lime
3440 - 3463	Lime
3463 - 3510	Shale and Lime
3510 - 3645	Lime
3645 - 3705	Shale and Lime
3705 - 3874	Lime
3874 - 3881	Shale
3881 - 3936	Lime
3936 - 3940	Shale
3940 - 3946	Sand
3946 - 3965	Sand
3965	Total Depth

2/21 RECEIVED
 STATE CORPORATION COMMISSION
 FEB 21 1957
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC. 16 T. 8 R. 25W
 BOOK PAGE 142 LINE 21



Subscribed and sworn to before me
 this 20th day of February, 1957
 My Commission expires Feb. 23, 1959

[Signature]
 Superintendent
Cecil J. Yerkes, Jr.
 Notary Public